



Straining posts supporting sports netting curtain system with clips to attach to perimeter fence at base. Posts to be designed as integral with fence post to minimise visual impact.

Storage area / void for storage of removeable divider panels complete with 6.0m wide double gate opening out into court but closing flush with boundary fence with no protruding parts, all designed to match boundary fence.

Single gate access at end of storage area.

Mass Concrete base under storage area & gate

Fencing to satisfy the following:

- To generally match velodrome fencing (british cycling spec)
- All galv only finish.
- Spectator rail required on outside (not offset), no running rail on inside.
- Clear perspex/ timber rebound board on inside face to 600mm high.
- Gates to open in or out 180 degrees (tbc)
- All to have soft netting 'curtain' above to height of 3.0m.
- Posts at 1.8m centres to match existing.

Removeable divider to satisfy the following:

- Must be easily installed / removed by 1 person.
- Must have mesh & rebound board (both sides) & netting above.
- Must clear fully away to leave a continuous useable full size court.
- No spectator rail / running rail required.
- Sockets installed flush into tarmac surface with lockable cover plates
- Each panel to be 1.5m wide to reduce weight for ease of installation

Installation

Total installation period expected to be 4-6 weeks from receipt of order and credit approval / deposit payment. Full programme to be submitted for approval prior to start of works but total period on site to be 2-3 weeks.

ARBUS LTD

CLIENT Herne Hill Velodrome
 CONTRACT Ballcourt
 CONTRACT NO AHS8662

DRAWN MK
 DATE 3-Aug-15

SUBJECT		
Ballcourt Proposal		
1	OF	1